GROSSMONT-CUYAMACA
COMMUNITY COLLEGE DISTRICT

Cuyamaca College Upgrade Electrical Panel



Project Budget: **$0.78 Million**
Construction Duration: **January 2016 – January 2017**
Funding Source: **Proposition V**

Scope/Summary:

This project included demolishing the existing 12kV SDGE metered service and relocate new service and equipment to exterior concrete pad. The new 12kV location will require earthwork, grading, new retaining wall, new concrete pad, fencing enclosure, and new equipment. The scope also includes the installation of a 3,000kVA transformer to back-feed power back to Building J.

Project Team:

- **General Contractor:** GA Technical Services, Inc.
- **Program Manager:** Penny McGrew, Gafcon, Inc.
- **Project Manager:** Eric Ganac, Gafcon, Inc.
- **Proposition V Program Manager:** Gafcon, Inc.